

EXHIBIT AH8

Independent Inspection Report VES-2261

Synthetic arbitration POC exhibit

Report date	22 April 2026
Client	Northbridge Renewables Limited
Inspection dates	20-21 April 2026
Location	Orchard Vale warehouse
Author	Dr Maya Chen, Principal Engineer

1. Instructions

Verity Engineering Services was instructed to inspect and test the 40 control units delivered to Northbridge's Orchard Vale warehouse on 12 April 2026.

2. Method

Inspection took place on 20 and 21 April. Each unit was visually inspected, opened to identify the processor board, checked for firmware version, and subjected to the contractual eight-hour thermal-soak test at 70 degrees Celsius.

3. Results

Test	Sample	Pass	Fail	Finding
Visual inspection	40	40	0	No shipping damage
Processor identity	40	0	40	ZR-41 installed; MX-46 specified
8-hour thermal soak at 70 C	40	9	31	Shutdown between 2.1 and 6.7 hours
Firmware check	40	40	0	Version 4.6.2

4. Conclusions

Thirty-one of the 40 units failed the required thermal-soak test. All 40 units contained a ZR-41 processor rather than the specified MX-46 processor. In Verity's opinion, the delivered batch does not conform to the technical requirements in clause 4 of the Supply Agreement.

5. Limitations

This report addresses the delivered batch only. Verity did not inspect the undelivered balance of 80 units.

Signed electronically by Dr Maya Chen, Principal Engineer, Verity Engineering Services, 22 April 2026.